



ADDENDUM #M01

August 18/16

SUBJECT: Faraday Community Centre - HVAC Upgrade

Please note the following and include in tender price:

- FOR THE NEW POURED CONCRETE SLAB - REMOVE EXISTING SOFT SPOTS, ANY ORGANIC AND FOREIGN MATERIAL TO A MINIMUM DEPTH OF 12 INCHES. INSTALL 4 INCHES OF COMPACTED PIT- RUN GRAVEL THE FINAL 8 INCHES TO BE COMPACTED GRANULAR "B" MATERIAL COMPACTION TO ACHIEVE A MINIMUM OF 98% STANDARD PROCTOR MAXIMUM DRY DENSITY. THE CONCRETE TO BE MINIMUM 20mPa, 6% AIR.
- PLASTIC PLUMBING VENT PIPING LOCATED ABOVE THE MEN'S WASHROOM CEILING IS TO BE RELOCATED AS NEEDED TO ALLOW FOR THE NEW A/C DUCTWORK IN THIS AREA.
- THE NEW ELECTRONIC PROGRAMMABLE THERMOSTATS FOR A/C-1 AND A/C-2 ARE TO BE PLACED IN THE SAME LOCATION AS THE EXISTING ELECTRO/MECHANICAL THERMOSTATS . NO REMOTE SENSORS ARE REQUIRED.

END OF ADDENDUM. Glenn Stapley, C.E.T. OTS Engineering

doc: 16044 Addendum M1.wpd